



---

Northwestern Water and Sewer District  
2024 Portage Water Main Replacement  
WL-306E

---

**ADDENDUM 2**

---

6/17/24

Planholders of the Northwestern Water and Sewer District, 2024 Portage Water Main Replacement, SS-306E, project are hereby notified of the following amendments to the Contract Documents. This Addendum is hereby made a part of the Contract Documents.

**QUESTIONS**

The following questions were submitted to the Engineer. The answers provided below are for the clarification of Bidders questions. Questions have been paraphrased for brevity.

***Question #1 – Will the engineer’s estimate be raised?***

No, not at this time.

***Question #2 – With the water main being installed deeper to account for road lowering, will the water services need to be installed deeper than 4’-0”?***

The new service will need to be installed with a minimum of 4’-6” of cover.

***Question #3 – Are Rieberlok Gaskets acceptable for joint restraint?***

No.

***Question #4 – If long or short water services are in rock, can they be open cut? Will we be paid for rock excavation & pavement?***

The bid should include the service installation as indicated in the Drawings and Specifications. If adjustments to installation methods are needed, they will be addressed once the project is awarded.

***Question #5 – What trench width should be used for this project?***

The trench width should be no wider than 6’ as shown on the pavement restoration sheets.

***Question #6 – For rock excavation, are we following that it has to be more than 6” thick to be compensated for rock removal per definition of Contract Items 14.04 4?***

Yes, see Specification 01010, 14.01, B.

**RECEIPT OF THIS ADDENDUM MUST BE ACKNOWLEDGED ON PAGE C-410 - 1 OF THE BID.**